


Bruhath Bengaluru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.

Schedule - B


Name of the Work : Construction of RCC drains at 8th cross left side in Santhosh Nagara in ward no. 13 Shettyhalli sub division

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted M/s M/s Nischal K Lakshman	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods Complete Asper the Directon Of Enggineer -in-charge of the work	CUM	345	175.96	Rupees One Hundred Seventy Five and Ninety Six Paisa Only
2	Removing B S Slab Drain And Stacking Asper the Directon Of Enggineer -in-charge of the work	SQM	465.75	65.72	Rupees Sixty Five and Seventy Two Paisa Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	41.1	4000.0	Rupees Four Thousand Only
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	5.48	5159.02	Rupees Five Thousand and One Hundred Fifty Nine and Two Paisa Only
5	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggretes @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	119.03	5500.0	Rupees Five Thousand and Five Hundred Only


Signature of the Contractor


Executive Engineer
Dasarhalli Division

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted M/s M/s Nischal K Lakshman	
				In Figures (Rs)	In Words (Rs)
6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting,. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour As per the Direction Of Engineer -in-charge of the work	Sqm	1242	270.0	Rupees Two Hundred and Seventy only
7	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery As per the Direction Of Engineer -in-charge of the work	Tonne	7.14	62000.0	Rupees Sixty Two Thousand Only
8	Providing & laying reinforced cement precast slabs of mix CC 1:1 1/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & As per the Direction Of Engineer -in-charge of the work	Sqm	34.56	1660.0	Rupee One Thousand and Six Hundred and Sixty Only


Signature of the Contractor

Executive Engineer
Dasarahalli Division
Bruhath Bengaluru Mahanagara Palike

Signature of the Contractor

Executive Engineer
Dasarahalli Division